DETAILED ESTIMATE · PWD SCHEDULE OF RATES

hospital (rerun, defaults)

Generated 10 Oct 2026, 14:51 · Status: **DRAFT**
1 · Construction cost (excl. land)

Rs 2,00,66,256.37

2 · With land: not entered
Built-up 1363.35 m² · Rs 1,367/sq ft

Rate source

Estimation scope	Entire property
Project location	Chennai, India
Rate authority	PWD — Public Works Department
Rate schedule	PWD Schedule of Rates 2025-26 — Vol I (incl. amendment)
Jurisdiction of the schedule	India
Year / financial year	2025 / 2025-26
Revision	Amendment Proceeding No. HDO/A/49517/2023 dated 08.08
Effective	2025-08-08
Source	PWD document (cross-verified): Schedule of rates 2025-26 - tnpwdea.org/files/tn-pwd-13-09-2025-05-30-44-133.pdf — SH 0cee169bde79524e6cc34a76266dc5b5a408691c62c4fd69d7
How it was selected	auto — PWD — latest validated applicable edition (2025-26, 2025-08-08)
Adjustments to schedule rates	none — schedule rates applied as published

1. Drawings used

File	Sheet	Type	Floor	Rooms	Used
demo_05_additional_4th__5th___6th_floors.png	Image	Floor plan	Typical floor — floors 4, 5, 6	18	yes

2. Parameters and where they came from

Parameter	Value	Source
Floors	3	1 floor plans covering 3 storey(s)
Floor height (m)	3.0	default
Plinth height (m)	0.6	default

Foundation depth (m)	1.5	default
Slab thickness (m)	0.125	default
Parapet height (m)	0.9	default
Sill height (m)	0.9	default
Lintel height (m)	2.1	default

3. Abstract of cost

#	Category	Amount	Share
1	RCC Works	Rs 24,67,334.98	15.1%
2	Formwork	Rs 22,62,210.61	13.8%
3	Reinforcement	Rs 29,65,227.02	18.1%
4	Masonry	Rs 15,62,730.15	9.5%
5	Plastering	Rs 15,11,166.96	9.2%
6	Flooring	Rs 13,88,209.89	8.5%
7	Painting	Rs 20,18,095.61	12.3%
8	Doors & Windows	Rs 12,21,442.85	7.5%
9	Waterproofing	Rs 7,69,493.25	4.7%
10	Electrical	Rs 1,85,700.00	1.1%
11	Plumbing & Sanitary	Rs 23,659.10	0.1%
	Sub-total (works)	**Rs 1,63,75,270.42**	
	Contingencies @ 3.0%	Rs 4,91,258.11	
	Labour welfare cess @ 1.0%	Rs 1,63,752.70	
	GST @ 18.0%	Rs 30,35,975.14	
	1. CONSTRUCTION COST (excl. land)	**Rs 2,00,66,256.37**	

Estimate status

PRELIMINARY — 24 line(s) use ASSUMED inputs (Rs 9,676,337); 11 line(s) depend on an unverified drawing scale (Rs 6,698,933); 14 line(s) priced at estimated (non-PWD) average rates (Rs 4,273,785); 1 identified element(s) not quantified — not in the total: Lift / elevator

Quantity status	Lines	Amount (Rs)	Meaning
PROVISIONAL	24	9,676,337	calculated with ASSUMED inputs (defaults / no structural drawing) — preliminary budgeting only, review

UNVERIFIED SCALE	11	6,698,933	drawing-derived, but the drawing scale is assumed — quantity scales with the unverified scale
EXCLUDED	11	1,740,940	outside the selected estimation scope — NOT in the total

Rate source (lines in the total)	Lines	Amount (Rs)	Meaning
PWD	21	12,101,485	PWD schedule rate / Standard Data analysis
ESTIMATED	14	4,273,785	estimated average rate (not a PWD rate)

Statuses overlap by design: a line can be PWD-priced and provisional. A priced line is not a validated line. Lines with a verified quantity: 0 of 35 counted lines (Rs 0).

Identified in the drawings but NOT quantified (not in the total): Lift / elevator

Not covered by the automatic take-off (add as items if part of the work): Fire-fighting / fire alarm, HVAC / air-conditioning, Lift equipment (car, machine, controls), Medical gases, External works (roads, drains, compound wall, landscaping), Electrical HT / transformer / DG set, Furniture & equipment

Floors: Typical floor — floors 4, 5, 6 (from '4TH , 5TH & 6TH FLOORS', confidence 0.98)

Estimate confidence: NEEDS REVIEW — structural input missing — structure quantities assumed; 100% of the priced amount needs review or is low confidence
NOT CALIBRATED — no labelled outcomes to calibrate against (validation-only calibration pending)

Structural: STRUCTURAL INPUT MISSING
• STRUCTURAL INPUT MISSING — no structural drawings / schedules: concrete member sizes and reinforcement cannot be derived

Areas — demo_05_additional_4th__5th___6th_floors.png (scale basis: ASSUMED scale (auto: external wall thickness 10.5px = 230 mm); NEEDS REVIEW)
carpet area: 296.85 m² (Σ usable area of private rooms (excl. walls, common areas); NEEDS REVIEW)
common area: 114.12 m² (Σ usable area of corridors, lobbies, stairs, lifts, shafts, refuge, services; NEEDS REVIEW)
plinth area: 454.45 m² (covered footprint at plinth level incl. walls (outer envelope); NEEDS REVIEW)
built up area: 454.45 m² (covered area of ONE floor incl. walls; NEEDS REVIEW)
gross floor area: 1,363.35 m² (Σ built-up area over the floors this plan stands for; NEEDS REVIEW)

Level	Check	Detail
WARNING	SCALE ASSUMED	scale basis: ASSUMED scale (auto: external wall thickness 10.5px = 230 mm) — review
CONFLICT	OPENING COUNT CONFLICT	window count disagrees between sources {'geometry': 12, 'detector': 0} — review; no source is chosen automatically
WARNING	FLOOR REPEAT NEEDS CONFIRMATION	'demo_05_additional_4th__5th___6th_floors.png' is applied to floors [4, 5, 6] because its text says '4TH , 5TH & 6TH FLOORS' — quantities are multiplied by 3. Confirm (or change) the floor on the drawing if the layout re
WARNING	STRUCTURAL INPUT MISSING	no structural drawing — footing / column / beam sizes and steel are ASSUMED

Assumptions & missing inputs

ID	Assumption	Value	Class	Cost affected (Rs)

P-FLOOR_HEIGHT	Floor-to-floor height	3.0 m	DEFAULT	
P-PLINTH_HEIGHT	Plinth height above ground	0.6 m	DEFAULT	
P-FOUNDATION_DEPTH	Foundation depth below ground	1.5 m	DEFAULT	
P-SLAB_THICKNESS	RCC slab thickness	0.125 m	DEFAULT	
P-PARAPET_HEIGHT	Parapet height	0.9 m	DEFAULT	
P-SILL_HEIGHT	Window sill height	0.9 m	DEFAULT	
P-LINTEL_HEIGHT	Lintel / door height	2.1 m	DEFAULT	
A-FOOTING	Footing sizes / footing steel assumed (no structural drawing)	—	ASSUMED	972,098
A-COLUMN	Column sizes / column steel assumed	—	ASSUMED	1,349,144
A-BEAM	Beams assumed under walls; beam steel assumed	—	ASSUMED	2,717,104
A-SLABSTEEL	Slab steel 90 kg/m³ assumed (no slab schedule)	—	ASSUMED	1,475,558
A-OPENING-H	Door / window heights from lintel & sill defaults (no schedule)	—	ASSUMED	1,154,972
A-DADO	Dado / skirting heights assumed	—	ASSUMED	11,445
A-SERVICES	Electrical / plumbing quantities from room norms (no services drawing)	—	ASSUMED	209,359
A-STAIR	Staircase waist and slope factor assumed	—	ASSUMED	205,470
A-PCC	Floor PCC 75 mm assumed	—	ASSUMED	254,290

Estimation scope: Entire property — PARTIAL estimate: lines outside this scope are listed below and are NOT in the total.

Measured but outside the selected scope (NOT in the total)

Item	Qty	Unit	Why excluded
Site clearance, clearing jungle, grass and vegetation over plinth area plus 50% working sp	681.67	sqm	upper-floor work only (floors 4, 5, 6) — no new foundation / ground-floor substructure; include foundation in the scope if this work needs it
Earth work excavation in foundation trenches for footings and plinth beams, lift up to 1.5	270.73	cum	upper-floor work only (floors 4, 5, 6) — no new foundation / ground-floor substructure; include foundation in the scope if this work needs it

Back filling excavated earth in trenches and sides of foundations in layers with ramming a	170.13	cum	upper-floor work only (floors 4, 5, 6) — no new foundation / ground-floor substructure; include foundation in the scope if this work needs it
Filling sand / murrum under floors in plinth with watering, ramming and consolidation	164.39	cum	upper-floor work only (floors 4, 5, 6) — no new foundation / ground-floor substructure; include foundation in the scope if this work needs it
Anti termite pre-constructional soil treatment with chlorpyriphos over plinth area	454.45	sqm	upper-floor work only (floors 4, 5, 6) — no new foundation / ground-floor substructure; include foundation in the scope if this work needs it
Plain cement concrete 1:4:8 lean concrete bed below footings and plinth beams with 40 mm a	27.73	cum	upper-floor work only (floors 4, 5, 6) — no new foundation / ground-floor substructure; include foundation in the scope if this work needs it
Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 grade	30.82	cum	upper-floor work only (floors 4, 5, 6) — no new foundation / ground-floor substructure; include foundation in the scope if this work needs it
Providing and laying in position reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse	41.51	cum	upper-floor work only (floors 4, 5, 6) — no new foundation / ground-floor substructure; include foundation in the scope if this work needs it
Centering and shuttering including strutting, propping etc. and removal of form for founda	269.53	sqm	upper-floor work only (floors 4, 5, 6) — no new foundation / ground-floor substructure; include foundation in the scope if this work needs it
Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in	3,321.00	kg	upper-floor work only (floors 4, 5, 6) — no new foundation / ground-floor substructure; include foundation in the scope if this work needs it
Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in	45.66	cum	upper-floor work only (floors 4, 5, 6) — no new foundation / ground-floor substructure; include foundation in the scope if this work needs it

Items priced at estimated average rates

No schedule rate is available for these items; an average rate was applied and can be edited.

Item	Unit	Rate (Rs)	Basis
Centering and shuttering including strutting, propping etc. and removal of form for suspen	sqm	927.25	reference schedule average — editable
Centering and shuttering including strutting, propping etc. and removal of form for lintel	sqm	736.40	reference schedule average — editable
Centering and shuttering including strutting, propping etc. and removal of form for column	sqm	961.30	reference schedule average — editable
Providing and applying white cement based putty over the plastered wall surface	sqm	156.05	reference schedule average — editable
Providing and fixing ISI marked flush door shutters conforming to IS : 2202 non-decorative	sqm	2,392.65	reference schedule average — editable

Providing and fixing door frame 100 mm x 60 mm, measured in running metre	metre	705.85	reference schedule average — editable
Aluminium sliding windows anodised with 5 mm glass glazing	sqm	3,250.00	market average — editable
Providing and fixing M.S. grills of required pattern in frames of windows fixed to opening	kg	219.10	reference schedule average — editable
Electrical wiring light point fan point with modular switch and copper conductor	point	650.00	market average — editable
Electrical wiring power socket outlet 6A/16A points	point	1,000.00	market average — editable
Distribution board with MCB and RCCB per floor	each	8,500.00	engineering estimate — editable
Wash basin with fittings and pillar tap	each	1,339.70	reference schedule average — editable
UPVC SWR soil and waste pipes 110 mm	metre	480.00	engineering estimate — editable
Overhead PVC water storage tank capacity in litres	litre	11.00	reference schedule average — editable

Other construction elements identified (not quantified)

Element	Where	Status
Lift / elevator	demo_05_additional_4th__5th___6th_floors.png Image	identified — needs quantity / user input (not in total)

4. Detailed estimate with traceability

#	Item · PWD item · measurement · drawing elements	Qty	Unit	PWD rate	Cost
RCC Works					**Rs 24,67,334.98**
9	**Reinforced cement concrete work in walls, columns, pillars, piers, abutments, posts and struts up to floor five level 1:1.5:3 graded stone aggregate 20 mm nominal size** PWD/SOR RA:rcc_column Standard Data 163: Providing and laying in position, standardised concrete Mix M-20 Grade using In-situ Concre · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **PROVISIONAL** · Rate: **PWD** · Basis: assumed 230×400 — no column schedule (assumed) > Measured: C (assumed): 41 × 0.23×0.40 × height 10.28 m (below GL 1.05 + plinth 0.6 + 3 × 3.0 m – 3 × slab 0.125 m) > From: demo_05_additional_4th__5th___6th_floors.png · Image	38.76	cum	Rs 7,707.05	Rs 2,98,725.26

10	**Reinforced cement concrete work in beams, suspended floors, roofs, landings, lintels, plinth beams up to floor five level 1:1.5:3 graded stone aggregate 20 mm nominal size** PWD/SOR RA:rcc_beam Standard Data 163: Providing and laying in position, standardised concrete Mix M-20 Grade using In-situ Concre · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **PROVISIONAL** · Rate: **PWD** · Basis: assumed under all walls — no beam schedule (assumed) > Measured: PB (assumed): 264.7 m × 0.23 × 0.300; B (assumed, Typical floor — floors 4, 5, 6): 794.2 m × 0.23 × 0.325 (floor beams measured below slab) From: demo_05_additional_4th__5th___6th_floors.png · Image	77.63	cum	Rs 7,707.05	Rs 5,98,298.29
11	**Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15 degrees, landings up to floor five level 1:1.5:3 graded stone aggregate 20 mm nominal size** PWD/SOR RA:rcc_slab Standard Data 163: Providing and laying in position, standardised concrete Mix M-20 Grade using In-situ Concre · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **PROVISIONAL** · Rate: **PWD** · Basis: drawing area; slab thickness: assumed default (slab_thickness) (partly assumed) > Measured: Typical floor — floors 4, 5, 6 454.4 m² × 3 × 0.125 m thick From: building outline	170.42	cum	Rs 7,707.05	Rs 13,13,435.46
12	**Reinforced cement concrete work in beams, lintels, bressumers over openings up to floor five level 1:1.5:3 graded stone aggregate 20 mm nominal size** PWD/SOR RA:rcc_lintel Standard Data 163: Providing and laying in position, standardised concrete Mix M-20 Grade using In-situ Concre · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **PROVISIONAL** · Rate: **PWD** · Basis: drawing openings; lintel section 230×150 assumed (partly assumed) > Measured: Σ (opening width + 0.30 bearing) × 0.23 × 0.15 over 38 openings × floors From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): openings door×26, window×12	6.67	cum	Rs 7,707.05	Rs 51,406.02

13	**Reinforced cement concrete in staircase waist slab, landings and steps 1:1.5:3 (M20)** PWD/SOR RA:rcc_stair Standard Data 163: Providing and laying in position, standardised concrete Mix M-20 Grade using In-situ Concre · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **PROVISIONAL** · Rate: **PWD** · Basis: drawing stair area; waist 150 mm and slope factor 1.30 assumed (no stair section) (partly assumed) > Measured: Σ stair-room plan area × 0.15 m waist × 1.30 (slope & steps) × storeys > From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): rooms LIFT, STAIR	26.66	cum	Rs 7,707.05	Rs 2,05,469.95
Formwork					**Rs 22,62,210.61**
15	**Centering and shuttering including strutting, propping etc. and removal of form for suspended floors, roofs, landings, balconies and access platform** PWD/SOR EST:fw_slab Estimated average rate — reference schedule average — editable · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · estimated average rate (editable) · map 0% Quantity: **UNVERIFIED SCALE** · Rate: **ESTIMATED** · Basis: drawing (derived) > Measured: Slab soffit = Σ carpet area × storeys > From: demo_05_additional_4th__5th___6th_floors.png · Image	1,232.91	sqm	Rs 927.25	Rs 11,43,215.80
16	**Centering and shuttering including strutting, propping etc. and removal of form for lintels, beams, plinth beams, girders, bressumers and cantilevers** PWD/SOR EST:fw_beam Estimated average rate — reference schedule average — editable · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · estimated average rate (editable) · map 0% Quantity: **PROVISIONAL** · Rate: **ESTIMATED** · Basis: assumed under all walls — no beam schedule (assumed) > Measured: Floor/roof beams (b + 2×(d – slab)) × L + lintel soffit & sides > From: demo_05_additional_4th__5th___6th_floors.png · Image	801.34	sqm	Rs 736.40	Rs 5,90,106.78

17	**Centering and shuttering including strutting, propping etc. and removal of form for columns, pillars, piers, abutments, posts and struts** PWD/SOR EST:fw_col Estimated average rate — reference schedule average — editable · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · estimated average rate (editable) · map 0% Quantity: **PROVISIONAL** · Rate: **ESTIMATED** · Basis: assumed 230×400 — no column schedule (assumed) > Measured: Σ n × perimeter 2(b+d) × 10.65 m > From: demo_05_additional_4th__5th___6th_floors.png · Image	550.18	sqm	Rs 961.30	Rs 5,28,888.03
Reinforcement					**Rs 29,65,227.02**
19	**Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding, Thermo-Mechanically Treated bars of grade Fe-500D, in columns** PWD/SOR RA:steel_column Standard Data 168: Supplying, fabricating and placing in position Mild Steel / Ribbed Tor Steel reinforcement · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **PROVISIONAL** · Rate: **PWD** · Basis: assumed bars 4-16 + 2-12, ties 8@150 (no column bar schedule) (assumed) > Measured: Main bars × (height 10.65 m + lap 50d per storey) + ties (perimeter – cover + hooks) at spacing > From: demo_05_additional_4th__5th___6th_floors.png · Image	5,609.67	kg	Rs 92.97	Rs 5,21,531.02
20	**Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding, Thermo-Mechanically Treated bars of grade Fe-500D, in beams** PWD/SOR RA:steel_beam Standard Data 168: Supplying, fabricating and placing in position Mild Steel / Ribbed Tor Steel reinforcement · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **PROVISIONAL** · Rate: **PWD** · Basis: assumed bars 2-12 top / 2-12 or 3-16 bottom, stirrups 8@150 (no beam bar schedule) (assumed) > Measured: Top + bottom bars × length × 1.12 (anchorage & laps) + stirrups at spacing > From: demo_05_additional_4th__5th___6th_floors.png · Image	10,413.45	kg	Rs 92.97	Rs 9,68,138.45

21	**Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding, Thermo-Mechanically Treated bars of grade Fe-500D, in slabs and lintels** PWD/SOR RA:steel_slab Standard Data 168: Supplying, fabricating and placing in position Mild Steel / Ribbed Tor Steel reinforcement · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **PROVISIONAL** · Rate: **PWD** · Basis: assumed — 90 kg/m³ slab, 80 kg/m³ lintels (no slab schedule) (assumed) > Measured: Slab concrete 170.4 m³ × 90 kg/m³ (assumed — no slab schedule) + lintels 6.67 m³ × 80 kg/m³ > From: building outline	15,871.33	kg	Rs 92.97	Rs 14,75,557.55
Masonry					**Rs 15,62,730.15**
23	**Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in cement mortar 1:6 (1 cement : 6 coarse sand)** PWD/SOR RA:mas_230 Standard Data 194: Brick work in following Cement Mortar using best quality Burnt Clay Brick of size 9” x 4 1/ · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **PROVISIONAL** · Rate: **PWD** · Basis: drawing wall lengths & openings; floor height: assumed default (floor_height); beam depth assumed (partly assumed) > Measured: Typical floor — floors 4, 5, 6: (95.1 m × 2.55 – 23.6 m² openings) × 0.115 × 3 (wall height = floor 3.0 – beam 0.45) > From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): 43 external wall segments	75.49	cum	Rs 7,425.62	Rs 5,60,560.05
24	**Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in cement mortar 1:4 (1 cement : 4 coarse sand)** PWD/SOR RA:mas_115 Standard Data 194: Brick work in following Cement Mortar using best quality Burnt Clay Brick of size 9” x 4 1/ · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **PROVISIONAL** · Rate: **PWD** · Basis: drawing wall lengths & doors; parapet 0.9 m: assumed default (parapet_height) (partly assumed) > Measured: Typical floor — floors 4, 5, 6: (169.7 m × 2.55 – 70.1 m² doors) × 3; parapet 95.5 m × 0.9 m > From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): 17 internal wall segments	1,173.57	sqm	Rs 853.95	Rs 10,02,170.10
Plastering					**Rs 15,11,166.96**

25	**12 mm cement plaster of mix 1:6 (1 cement : 6 coarse sand) on internal walls** PWD/SOR RA:plaster_int Standard Data 298: Plastering with Cement Mortar 1:6 (One cement and Six Plastering sand), 12mm thick in all f · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **UNVERIFIED SCALE** · Rate: **PWD** · Basis: drawing (derived) > Measured: Σ per floor (room perimeters × 2.875 m – openings) × storeys From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): rooms WARD-1, WARD, WARD, WARD-4, WARD, CORE, NURSE, CORRIDOR, SERVICE, LIFT, STAIR, SHAFT, WARD, WARD, WARD, WARD, WARD-10, CORE	2,488.80	sqm	Rs 282.24	Rs 7,02,438.91
26	**6 mm cement plaster 1:3 to ceiling underside of RCC slab** PWD/SOR RA:plaster_ceil Standard Data 302: Special ceiling plastering and finishing the exposed surface of all RCC items of work such · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **UNVERIFIED SCALE** · Rate: **PWD** · Basis: drawing (derived) > Measured: Σ carpet area × storeys From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): rooms WARD-1, WARD, WARD, WARD-4, WARD, CORE, NURSE, CORRIDOR, SERVICE, LIFT, STAIR, SHAFT, WARD, WARD, WARD, WARD, WARD-10, CORE	1,232.91	sqm	Rs 329.85	Rs 4,06,675.36
27	**15 mm cement plaster on rough side of single or half brick wall of mix 1:4 (1 cement : 4 coarse sand) on external walls** PWD/SOR RA:plaster_ext Standard Data 300: Plastering with Cement Mortar 1:5 (One cement and Five Plastering sand), 15mm thick in all · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **UNVERIFIED SCALE** · Rate: **PWD** · Basis: drawing (derived) > Measured: Σ envelope perimeter × 3.0 m – openings per floor + plinth 0.6 m + parapet both faces 0.9 m From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): 43 external wall segments	1,018.19	sqm	Rs 394.87	Rs 4,02,052.69
Flooring					**Rs 13,88,209.89**

28	**Providing and laying vitrified floor tiles 600×600 mm on cement mortar in living, bedrooms and kitchen** PWD/SOR RA:floor_vit Standard Data 256: Paving the floor with best quality vitrified Tiles of following size and variety conforming · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **UNVERIFIED SCALE** · Rate: **PWD** · Basis: drawing (derived) > Measured: Σ dry room areas × storeys From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): rooms CORRIDOR, LIFT, STAIR	205.23	sqm	Rs 1,569.95	Rs 3,22,200.84
29	**Providing and laying ceramic glazed floor tiles of size 300x300 mm in toilets, bathrooms and wet areas** PWD/SOR RA:floor_antiskid Standard Data 257: Flooring with ceramic tiles of following size and variety conforming to IS 15622 laid over · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **UNVERIFIED SCALE** · Rate: **PWD** · Basis: drawing (derived) > Measured: Σ wet room areas × storeys From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): rooms WARD-1, WARD, WARD, WARD-4, WARD, CORE, NURSE, SERVICE, SHAFT, WARD, WARD, WARD, WARD, WARD-10, CORE	1,027.68	sqm	Rs 1,026.16	Rs 10,54,564.11
30	**Providing and laying vitrified floor tiles 600x600 mm as skirting in dry rooms** PWD/SOR RA:skirting Standard Data 256: Paving the floor with best quality vitrified Tiles of following size and variety conforming · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **PROVISIONAL** · Rate: **PWD** · Basis: drawing perimeters; skirting height 100 mm assumed (partly assumed) > Measured: (Σ dry room perimeters − door widths) × 0.10 From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): rooms CORRIDOR, LIFT, STAIR	7.29	sqm	Rs 1,569.95	Rs 11,444.94
Painting					**Rs 20,18,095.61**

31	**Providing and applying white cement based putty over the plastered wall surface** PWD/SOR EST:putty Estimated average rate — reference schedule average — editable · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · estimated average rate (editable) · map 0% Quantity: **UNVERIFIED SCALE** · Rate: **ESTIMATED** · Basis: drawing (derived) > Measured: Internal plaster + ceiling – toilet dado From: demo_05_additional_4th__5th___6th_floors.png · Image	3,721.71	sqm	Rs 156.05	Rs 5,80,772.85
32	**Acrylic emulsion paint interior walls and ceilings two coats** PWD/SOR RA:paint_int Standard Data 373: Painting New Plastered Wall Surface with Two finishing coats of ready mixed (Emulsion) of a · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **UNVERIFIED SCALE** · Rate: **PWD** · Basis: drawing (derived) > Measured: Internal plaster + ceiling – toilet dado From: demo_05_additional_4th__5th___6th_floors.png · Image	3,721.71	sqm	Rs 277.39	Rs 10,32,365.14
33	**Finishing walls with Acrylic Smooth exterior paint of required shade new work two or more coats including priming coat of exterior primer** PWD/SOR RA:paint_ext Standard Data 373: Painting New Plastered Wall Surface with Two finishing coats of ready mixed (Emulsion) of a · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **UNVERIFIED SCALE** · Rate: **PWD** · Basis: drawing (derived) > Measured: = external plaster area From: demo_05_additional_4th__5th___6th_floors.png · Image	1,018.19	sqm	Rs 280.06	Rs 2,85,154.29
34	**Painting with synthetic enamel paint of approved brand and manufacture to give an even shade two or more coats on new work, doors and grills** PWD/SOR RA:paint_enamel Standard Data 363: Painting new wood work with two finishing coats of synthetic enamel ready mixed paint of ap · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · Standard Data analysis · map 100% Quantity: **PROVISIONAL** · Rate: **PWD** · Basis: drawing widths; heights assumed (lintel 2.1 m, sill 0.9 m) — no door/window schedule (partly assumed) > Measured: Door area × 2 faces + grills 0.5 × window area From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): openings door×26	455.89	sqm	Rs 262.79	Rs 1,19,803.33

Doors & Windows					**Rs 12,21,442.85**
35	**Providing and fixing ISI marked flush door shutters conforming to IS : 2202 non-decorative type 35 mm thick including stainless steel butt hinges** PWD/SOR EST:door_shutter Estimated average rate — reference schedule average — editable · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · estimated average rate (editable) · map 0% Quantity: **PROVISIONAL** · Rate: **ESTIMATED** · Basis: drawing widths; heights assumed (lintel 2.1 m, sill 0.9 m) — no door/window schedule (partly assumed) > Measured: 0.58×2.10: 6 × 0.58×2.10; 0.59×2.10: 3 × 0.59×2.10; 0.61×2.10: 9 × 0.61×2.10; 0.70×2.10: 3 × 0.70×2.10; 0.71×2.10: 3 × 0.71×2.10; 1.42×2.10: 6 × 1.42×2.10; 1.45×2.10: 12 × 1.45×2.10; 1.62×2.10: 6 × 1.62×2.10; 1.65×2.10: 30 × 1.65×2.10 (door height 2.1 m, windows 1.20 m (lintel – sill)) > From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): openings door×26	210.23	sqm	Rs 2,392.65	Rs 5,03,006.81
36	**Providing and fixing door frame 100 mm x 60 mm, measured in running metre** PWD/SOR EST:door_frame Estimated average rate — reference schedule average — editable · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · estimated average rate (editable) · map 0% Quantity: **PROVISIONAL** · Rate: **ESTIMATED** · Basis: drawing widths; heights assumed (lintel 2.1 m, sill 0.9 m) — no door/window schedule (partly assumed) > Measured: Σ (2 × height + width) per door × storeys > From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): openings door×26	427.71	metre	Rs 705.85	Rs 3,01,899.10
37	**Aluminium sliding windows anodised with 5 mm glass glazing** PWD/SOR EST:window_alu Estimated average rate — market average — editable · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · estimated average rate (editable) · map 0% Quantity: **PROVISIONAL** · Rate: **ESTIMATED** · Basis: drawing widths; heights assumed (lintel 2.1 m, sill 0.9 m) — no door/window schedule (partly assumed) > Measured: 1.52×1.20: 18 × 1.52×1.20; 1.75×1.20: 12 × 1.75×1.20; 1.78×1.20: 6 × 1.78×1.20 (door height 2.1 m, windows 1.20 m (lintel – sill)) > From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): openings window×12	70.85	sqm	Rs 3,250.00	Rs 2,30,262.50

38	**Providing and fixing M.S. grills of required pattern in frames of windows fixed to openings with rawl plugs screws** PWD/SOR EST:grills Estimated average rate — reference schedule average — editable · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · estimated average rate (editable) · map 0% Quantity: **PROVISIONAL** · Rate: **ESTIMATED** · Basis: drawing window area; grill weight 12 kg/m² assumed (partly assumed) > Measured: Window area × 12 kg/m² > From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): openings window×12	850.18	kg	Rs 219.10	Rs 1,86,274.44

Waterproofing		**Rs 7,69,493.25**

39	**Roof terrace waterproofing with brick bat coba and membrane** PWD/SOR W-0302 Newly Constructed Roof / Bathroom/Toilet/ balcony/utility with Cementatius Waterproof coating below 500 Sq.m - · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · SOR item rate · map 100% Quantity: **UNVERIFIED SCALE** · Rate: **PWD** · Basis: drawing (derived) > Measured: Roof = top floor plinth 454.45 m² > From: building outline	454.45	sqm	Rs 555.00	Rs 2,52,219.75
40	**Cementitious waterproofing coating in toilets and wet areas floor plus 300 mm upturn** PWD/SOR W-0301 Newly Constructed Bathroom / toilet / balcony / utility with Cementatius Waterproof coating below 300 Sq.m - P · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · SOR item rate · map 100% Quantity: **UNVERIFIED SCALE** · Rate: **PWD** · Basis: drawing (derived) > Measured: Σ (wet area + perimeter × 0.3) × storeys > From: demo_05_additional_4th__5th___6th_floors.png Image (Typical floor — floors 4, 5, 6): rooms WARD-1, WARD, WARD, WARD-4, WARD, CORE, NURSE, SERVICE, SHAFT, WARD, WARD, WARD, WARD, WARD-10, CORE	1,286.75	sqm	Rs 402.00	Rs 5,17,273.50

Electrical		**Rs 1,85,700.00**

41	**Electrical wiring light point fan point with modular switch and copper conductor** PWD/SOR EST:elec_light Estimated average rate — market average — editable · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · estimated average rate (editable) · map 0% Quantity: **PROVISIONAL** · Rate: **ESTIMATED** · Basis: assumed — norm per room / fixture (no services drawing) (assumed) > Measured: Σ room-type norms (living 6, bedroom 4, kitchen 3 …) > From: demo_05_additional_4th__5th___6th_floors.png · Image	108.00	point	Rs 650.00	Rs 70,200.00
42	**Electrical wiring power socket outlet 6A/16A points** PWD/SOR EST:elec_power Estimated average rate — market average — editable · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · estimated average rate (editable) · map 0% Quantity: **PROVISIONAL** · Rate: **ESTIMATED** · Basis: assumed — norm per room / fixture (no services drawing) (assumed) > Measured: Σ room-type norms > From: demo_05_additional_4th__5th___6th_floors.png · Image	90.00	point	Rs 1,000.00	Rs 90,000.00
43	**Distribution board with MCB and RCCB per floor** PWD/SOR EST:elec_db Estimated average rate — engineering estimate — editable · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · estimated average rate (editable) · map 0% Quantity: **PROVISIONAL** · Rate: **ESTIMATED** · Basis: assumed — norm per room / fixture (no services drawing) (assumed) > Measured: 1 per floor × 3 > From: demo_05_additional_4th__5th___6th_floors.png · Image	3.00	each	Rs 8,500.00	Rs 25,500.00
Plumbing & Sanitary					**Rs 23,659.10**
44	**Wash basin with fittings and pillar tap** PWD/SOR EST:basin Estimated average rate — reference schedule average — editable · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · estimated average rate (editable) · map 0% Quantity: **PROVISIONAL** · Rate: **ESTIMATED** · Basis: assumed — norm per room / fixture (no services drawing) (assumed) > Measured: 1 per toilet + 1 per floor > From: demo_05_additional_4th__5th___6th_floors.png · Image	3.00	each	Rs 1,339.70	Rs 4,019.10

45	**UPVC SWR soil and waste pipes 110 mm** PWD/SOR EST:swr Estimated average rate — engineering estimate — editable · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · estimated average rate (editable) · map 0% Quantity: **PROVISIONAL** · Rate: **ESTIMATED** · Basis: assumed — norm per room / fixture (no services drawing) (assumed) > Measured: 8 m per toilet + 2 vertical stacks From: demo_05_additional_4th__5th___6th_floors.png · Image	18.00	metre	Rs 480.00	Rs 8,640.00
46	**Overhead PVC water storage tank capacity in litres** PWD/SOR EST:tank Estimated average rate — reference schedule average — editable · PWD Schedule of Rates 2025-26 — Vol I (incl. amendment) · rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · PWD 2025 / 2025-26 / rev. Amendment Proceeding No. HDO/A/49517/2023 dated 08.08.2025 · estimated average rate (editable) · map 0% Quantity: **PROVISIONAL** · Rate: **ESTIMATED** · Basis: assumed — norm per room / fixture (no services drawing) (assumed) > Measured: 1 bedrooms × 2 persons × 135 lpcd × 1.5 day From: demo_05_additional_4th__5th___6th_floors.png · Image	1,000.00	litre	Rs 11.00	Rs 11,000.00

Rates are taken only from the rate schedule shown under "Rate source". Quantities come from the drawings and do not depend on the location. Highlighted rows need estimator review.

Prepared by	Checked by	Approved by